

ಸಂಕ್ಷಿಪ್ತ ಟೆಂಡರ್ ಅಧಿಸೂಚನೆ

ಈ ಮೂಲಕ ಸಾರ್ವಜನಿಕರಿಗೆ ತಿಳಿಯ ಪಡಿಸುವುದೇನೆಂದರೆ ಈ ಅಧಿಸೂಚನೆಯೊಂದಿಗೆ ಲಗತ್ತಿಸಿರುವ ಅನುಸೂಚಿ (Annexure) ಯಲ್ಲಿ ನಮೂದಿಸಿರುವ ಅರಣ್ಯ ಪ್ರದೇಶದಲ್ಲಿ ಅರಣ್ಯೀಕರಣ ಕಾಮಗಾರಿಗಳು ಹಾಗೂ ಸಿವಿಲ್ ಕಾಮಗಾರಿಗಳನ್ನು 2006-07 ನೇ ಸಾಲಿನಲ್ಲಿ ನಿರ್ವಹಿಸಲು ಅರಣ್ಯ ಇಲಾಖೆಯಲ್ಲಿ ಹೆಸರನ್ನು ನೋಂದಾಯಿಸಿಕೊಂಡಿರುವ ಅರಣ್ಯ ಗುತ್ತಿಗೆದಾರರಿಂದ ಮೊಹರಾದ ಟೆಂಡರ್‌ನ್ನು ಈಗಾಗಲೇ ದಿನಾಂಕ : 20.07.2006, 25.07.2006 ಹಾಗೂ 31.07.2006 ರಂದು ಕರೆಯಲಾಗಿ ಇವುಗಳು ತಿರಸ್ಕೃತಗೊಂಡ ಕಾರಣ ಅನುಸೂಚಿಯಲ್ಲಿ ನಮೂದಿಸಿರುವ ಯುನಿಟ್‌ಗಳಿಗೆ ದಿನಾಂಕ : 06.10.2006 ರಂದು ಟೆಂಡರ್‌ನ್ನು ಕರೆಯಲಾಗಿದೆ. ಹಾಗೂ ಈ ಟೆಂಡರ್‌ನ್ನು ಮಧ್ಯಾಹ್ನ 3:30 ಗಂಟೆಯವರೆಗೆ ಸ್ವೀಕರಿಸಲಾಗುವುದು. ಟೆಂಡರ್ ಫಾರಂಗಳನ್ನು ಟೆಂಡರ್ ಫಾರಂ ಬೆಲೆ ಮತ್ತು ಚಾಲ್ತಿಯಲ್ಲಿರುವ ತೆರಿಗೆಗಳನ್ನು ಪಾವತಿಸಿ ಈ ಕಛೇರಿಯಲ್ಲಿ ದಿನಾಂಕ : 28.09.2006 ರಿಂದ 06.10.2006 ರ ಮಧ್ಯಾಹ್ನ 3:30 ಗಂಟೆಯವರೆಗೆ ಪಡೆಯಬಹುದು. ಸ್ವೀಕರಿಸಲಾದ ಟೆಂಡರ್‌ಗಳನ್ನು ದಿನಾಂಕ : 06.10.2006 ರಂದು ಮಧ್ಯಾಹ್ನ 4:00 ಗಂಟೆಗೆ ಹಾಜರಿರುವ ಅರಣ್ಯ ಗುತ್ತಿಗೆದಾರರ ಸಮಕ್ಷಮ ಈ ಕೆಳ ಸಹಿ ಮಾಡಿರುವ ಅಧಿಕಾರಿಗಳು ಅಥವಾ ಅವರಿಂದ ಪ್ರಾಧಿಕೃತಗೊಂಡ ಅಧಿಕಾರಿಗಳಿಂದ ತೆರೆಯಲಾಗುವುದು. ಒಂದು ವೇಳೆ ಟೆಂಡರ್ ದಿನಾಂಕವು ಸಾರ್ವಜನಿಕ ರಜೆಯೆಂದು ಘೋಷಿತವಾದಲ್ಲಿ ಮರು ದಿನ ಟೆಂಡರ್‌ನ್ನು ಸ್ವೀಕರಿಸಿ ಅದೇ ಸಮಯಕ್ಕೆ ತೆರೆಯಲಾಗುವುದು. ದಿನಾಂಕ: 06.10.2006 ರಂದು ಟೆಂಡರ್‌ನಲ್ಲಿ ಯಾರು ಭಾಗವಹಿಸದ ಪಕ್ಷದಲ್ಲಿ ದಿನಾಂಕ : 13.10.2006 ರಂದು ಮಧ್ಯಾಹ್ನ 3:30 ಗಂಟೆಯ ವರೆಗೆ ಟೆಂಡರ್ ಫಾರಂ ವಿತರಿಸಿ ಮರು ಟೆಂಡರ್‌ನ್ನು ಮಧ್ಯಾಹ್ನ 3:30 ಗಂಟೆಯವರೆಗೆ ಸ್ವೀಕರಿಸಿ, ಮಧ್ಯಾಹ್ನ 4:00 ಗಂಟೆಗೆ ತೆರೆಯಲಾಗುವುದು. ಈ ಮೇಲ್ಕಂಡ ಎರಡೂ ಟೆಂಡರ್‌ಗಳಲ್ಲಿ ಯಾರೂ ಭಾಗವಹಿಸದಿದ್ದಲ್ಲಿ ಅಥವಾ ಟೆಂಡರ್ ತಿರಸ್ಕೃತಗೊಂಡಲ್ಲಿ ಇಲಾಖಾ ಮುಖಾಂತರ ಈ ಕಾಮಗಾರಿಯನ್ನು ಕೈಗೊಳ್ಳಲಾಗುವುದು.

ಷರತ್ತುಗಳು

- 1) ಟೆಂಡರ್ ಫಾರಂ ದರ ರೂ: 200-00 ಗಳನ್ನು ಇತರೆ ಚಾಲ್ತಿಯಲ್ಲಿರುವ ತೆರಿಗೆ ಪಾವತಿಸಿ ದಿನಾಂಕ: 06.10.2006 (ಮರು ಟೆಂಡರ್‌ಗೆ ದಿನಾಂಕ : 13.10.2006) ಮಧ್ಯಾಹ್ನ 3:30 ಗಂಟೆಯವರೆಗೆ ಪಡೆಯಬಹುದು. ಹಾಗೂ ಟೆಂಡರ್‌ನಲ್ಲಿ ಭಾಗವಹಿಸುವವರು ಪ್ರತೀ ಯುನಿಟ್‌ಗೆ ಪ್ರತ್ಯೇಕ ಟೆಂಡರ್ ಫಾರ್ಮ್ ಪಡೆಯುವುದು.
- 2) ಈ ಕಾಮಗಾರಿಯನ್ನು ನಿಗದಿ ಪಡಿಸಿರುವ ಇಲಾಖೆಯ ಎಸ್.ಎಸ್.ಆರ್ ನಂತೆ ನಿರ್ವಹಿಸಬೇಕು ಹಾಗೂ ದರವನ್ನು ನಮೂದಿಸುವಾಗ ಎಸ್.ಎಸ್.ಆರ್ ದರದ ಮೇಲೆ ಶೇಕಡವಾರು ದರವನ್ನು ಸ್ಪಷ್ಟವಾಗಿ ಅಂಕಿ ಮತ್ತು ಅಕ್ಷರಗಳಲ್ಲಿ ನಮೂದಿಸಬೇಕು. ಹಾಗೂ ಎಸ್.ಎಸ್.ಆರ್ ದರಕ್ಕಿಂತ ಹೆಚ್ಚಿನ ದರವಾದಲ್ಲಿ ಸದರಿ ಟೆಂಡರ್‌ನ್ನು ತಿರಸ್ಕರಿಸಲಾಗುವುದು. ಮತ್ತು ಈ ದರವು ನಿಗದಿ ಪಡಿಸಿರುವ ಕಾಮಗಾರಿಯ ಕಾನ್ಸ್ಟ್ರಾಕ್ಷನ್ ಗೆ ಸೀಮಿತವಾಗಿರತಕ್ಕದ್ದು.
- 3) ಕಾಮಗಾರಿ ಕೆಲಸವು ಅಂದಾಜಿನದಾಗಿದ್ದು, ಕಾಮಗಾರಿಗಳನ್ನು ಅನುದಾನಕ್ಕೆ ಹಾಗೂ ಪರಿಸ್ಥಿತಿಗೆ ಅನುಗುಣವಾಗಿ ರದ್ದುಗೊಳಿಸುವ ಮತ್ತು ಪರಿಷ್ಕರಿಸುವ ಅಧಿಕಾರ ಈ ಕೆಳ ಸಹಿದಾರರಿಗೆ ಇರುತ್ತದೆ.
- 4) ಈ ಕಾಮಗಾರಿಗಳಲ್ಲಿ ಅರಣ್ಯೀಕರಣ ಕಾಮಗಾರಿಗಳು ಅರಣ್ಯ ಪ್ರದೇಶದ ಒಳಗಡೆ ಇರುವುದರಿಂದ ಸ್ಥಳ ಪರಿಶೀಲನೆ ಮಾಡಿದ ನಂತರವೇ ಟೆಂಡರ್‌ನಲ್ಲಿ ಭಾಗವಹಿಸುವುದು.
- 5) ಕಾಮಗಾರಿಯ ವಿವರವಾದ ಪಟ್ಟಿಯನ್ನು ಈ ಕಛೇರಿಯಲ್ಲಿ ಪರಿಶೀಲಿಸಬಹುದಾಗಿದೆ.
- 6) ಟೆಂಡರ್‌ಗೆ ಇಟ್ಟಿರುವ ಅಂದಾಜು ಮೊಬಲಗಿನ ಮೇಲೆ ಅನುಸೂಚಿಯಲ್ಲಿ ನಮೂದಿಸಿರುವಂತೆ ಮುಂಗಡ ಠೇವಣಿ (ಇ.ಎಂ.ಡಿ.) ಯನ್ನು ಉಪ ಅರಣ್ಯ ಸಂರಕ್ಷಣಾಧಿಕಾರಿಗಳು, ಕೊಳ್ಳೇಗಾಲ ವಿಭಾಗ, ಕೊಳ್ಳೇಗಾಲ ರವರ ಹೆಸರಿನಲ್ಲಿ ಯಾವುದಾದರೂ ರಾಷ್ಟ್ರೀಕೃತ ಬ್ಯಾಂಕಿನಲ್ಲಿ ಡಿ.ಡಿ. ಯನ್ನು ಪಡೆದು ಕೊಳ್ಳೇಗಾಲದಲ್ಲಿ ಪಾವತಿ ಯಾಗುವಂತೆ ಪಡೆದು ಟೆಂಡರ್ ಫಾರಂನೊಂದಿಗೆ ಲಗತ್ತಿಸಬೇಕು ಹಾಗೂ ಮುಂಗಡ ಠೇವಣಿ ಹಣವನ್ನು ಲಗತ್ತಿಸದ ಟೆಂಡರ್‌ನ್ನು ನೇರವಾಗಿ ತಿರಸ್ಕರಿಸಲಾಗುವುದು.
- 7) ಟೆಂಡರ್‌ನ್ನು ಅಂಗೀಕರಿಸುವ ಅಥವಾ ನಿರಾಕರಿಸುವ ಅಧಿಕಾರ ಈ ಕೆಳ ಸಹಿ ಮಾಡಿರುವವರಿಗೆ ಅಥವಾ ಮೇಲಾಧಿಕಾರಿಗಳಿಗೆ ಕಾಯ್ದಿರಿಸಲಾಗಿದೆ.
- 8) ವಿಜೇತ ಟೆಂಡರುದಾರರು ಆದೇ ಶ ನೀಡಿದ 7 ದಿನಗಳೊಳಗಾಗಿ ಕರಾರು ಒಪ್ಪಂದವನ್ನು ಈ ಕೆಳ ಸಹಿದಾರರ ಸಮ್ಮುಖದಲ್ಲಿ ಮಾಡಿಕೊಳ್ಳತಕ್ಕದ್ದು.
- 9) ನಿಗದಿತ ಕಾಮಗಾರಿಯನ್ನು ನಿಬಂಧನೆಗೆ ಹಾಗೂ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಅನುಗುಣವಾಗಿ ಪೂರ್ಣಗೊಳಿಸಿ, ಸಹಾಯಕ ಅರಣ್ಯ ಸಂರಕ್ಷಣಾಧಿಕಾರಿರವರು ಕೈಗೊಂಡ ಕ್ಷೇತ್ರಗಳಿಗೆ ಅನುಸಾರವಾಗಿ ಹಣವನ್ನು ಪಾವತಿಸಲು ಕ್ರಮ ಕೈಗೊಳ್ಳಲಾಗುವುದು.
- 10) ಟೆಂಡರ್ ಪ್ರಕಟಣೆಯ ಯಾವುದೇ ನಿಯಮವನ್ನು ಉಲ್ಲಂಘಿಸಿದಲ್ಲಿ ಯಾವುದೇ ಮುನ್ಸೂಚನೆ ನೀಡದೆ ಇ.ಎಂ.ಡಿ ಹಣವನ್ನು ಮುಟ್ಟುಗೋಲು ಹಾಕಿಕೊಂಡು ಮರು ಟೆಂಡರು ಮಾಡಲಾಗುವುದು.
- 11) ಈ ಮೇಲ್ಕಂಡ ಷರತ್ತುಗಳಲ್ಲದೆ ವಿವರವಾದ ಷರತ್ತುಗಳಿಗಾಗಿ ಈ ಕಛೇರಿಯನ್ನು ಕಛೇರಿ ವೇಳೆಯಲ್ಲಿ ಸಂಪರ್ಕಿಸಬಹುದಾಗಿದೆ. ಅಥವಾ ಅರಣ್ಯ ಇಲಾಖೆಯ ವೆಬ್‌ಸೈಟ್ www.karnatakaforestdepartment.org ಯಲ್ಲಿ ಪರಿಶೀಲಿಸಬಹುದಾಗಿದೆ.

ಆಡಕ : ಕಾಮಗಾರಿಗಳ ವಿವರವಾದ ಅನುಸೂಚಿ - 3 ಪುಟಗಳು

ಉಪ ಅರಣ್ಯ ಸಂರಕ್ಷಣಾಧಿಕಾರಿ,
ಕೊಳ್ಳೇಗಾಲ ವಿಭಾಗ, ಕೊಳ್ಳೇಗಾಲ.

Annexure to the Forest and Civil works Tender dated : 06.10.2006

A) Tender for Excavation of Cattel proof Trench (CPT) as per the specification during the year 2006-07 under KSFMB								
Excavation of cattle proof trench of size top width 1.5 M. bottom 1.0 M. and vertical depth 1.0 M. with an initial lead up to 2 M. and depositing the excavated soil uniformly over the inner side of the CPT and forming conical mound of height 1.0 M., including manually compacting the mound by deploying JCB / Hitachi excavators $\left(\frac{1.5+1.0}{2}\right) \times 1.0 = 1.25 \times 1.0 = 1.25\text{m}^3/\text{Meter}$								
SSR Rate 36.00 /cum								
Unit No	Range / Model	Name of the Village	Section	Quantity in Ha	CPT in Cu.m	Maximum Amount	EMD Amount	Remarks
1	Kollegal Range							
	<i>Model 1</i>	Masibhovidoddi	P.G. Palya	25	2,150.00	77,400.00		Works to be carried out as per the above Specification. The total amount payable shall be based on the actual work done as per the above specification and limited to the amount mentioned for each work.
		Hosapalaimam	P.G. Palya	25	2,150.00	77,400.00		
					-	-		
	<i>Model 2</i>	Uganiya	Sathegal Jageri	25	2,250.00	81,000.00		
					-	-		
	<i>Model 3</i>	Hosadoddi	P.G. Palya	10	610.00	21,960.00		
		Masibhovidoddi	P.G. Palya	10	610.00	21,960.00		
		Munigudidoddi	P.G. Palya	30	1,830.00	65,880.00		
		Utturu	P.G. Palya	30	1,830.00	65,880.00		
		Hosapalaimam	P.G. Palya	10	610.00	21,960.00		
					-	-		
	<i>Model 4</i>	Masibhovidoddi	P.G. Palya	20	1,480.00	53,280.00		
		Uganiya	Sathegal Jageri	20	1,480.00	53,280.00		
		Munigudidoddi	P.G. Palya	20	1,480.00	53,280.00		
					-	-		
	<i>Model 5</i>	Masibhovidoddi	P.G. Palya	15	1,170.00	42,120.00		
		Uganiya	Sathegal Jageri	10	780.00	28,080.00		
		Hosapalaimam	P.G. Palya	20	1,560.00	56,160.00		
				270		719,640.00	18,000	
2	Hanur Range							
	<i>Model 1</i>	Kanchalli	Lokkanahalli	25	2,150.00	77,400.00		-Do-
					-	-		
	<i>Model 2</i>	Sahebaradoddi	Lokkanahalli	20	1,800.00	64,800.00		
		Lambani Doddi	Kothanur	20	1,800.00	64,800.00		
					-	-		
	<i>Model 3</i>	Achgallidoddi	Bandally	20	1,220.00	43,920.00		
		Sahebaradoddi	Lokkanahalli	20	1,220.00	43,920.00		
		Kanchalli	Lokkanahalli	10	610.00	21,960.00		
		Lambani Doddi	Kothanur	10	610.00	21,960.00		
					-	-		
	<i>Model 4</i>	Sahebaradoddi	Lokkanahalli	20	1,480.00	53,280.00		
		Kanchalli	Lokkanahalli	20	1,480.00	53,280.00		
		Lambani Doddi	Kothanur	10	740.00	26,640.00		
					-	-		
	<i>Model 5</i>	Achgallidoddi	Bandally	10	780.00	28,080.00		
		Sahebaradoddi	Lokkanahalli	10	780.00	28,080.00		
		Kanchalli	Lokkanahalli	10	780.00	28,080.00		
		Lambani Doddi	Kothanur	10	780.00	28,080.00		
				215		584,280.00	14,600	
4	Gundlupet Range							
	<i>Model 1</i>	Hangalada Hosahalli	Hangala	50	4,300.00	154,800.00		-Do-
					-	-		
	<i>Model 2</i>	Lokkere	Yelchetty	25	2,250.00	81,000.00		
					-	-		
	<i>Model 3</i>	Lokkere	Yelchetty	50	3,050.00	109,800.00		
					-	-		
	<i>Model 4</i>	Lokkere	Yelchetty	30	2,220.00	79,920.00		
					-	-		
	<i>Model 5</i>	Huliyammanagudi	Hangala	25	1,950.00	70,200.00		
		Lokkere	Yelchetty	10	780.00	28,080.00		
				190		523,800.00	13,100	

C) Tender for Excavation of pits as per the specification during the year 2006-07 under KSFMB								
Excavation of pits with vertically cut edges to make an uniform cube and heaping the excavated soil on the lower side of the pits (1/3 top soil on the upper side and lower side) in hard soil For Model 2 - pit size 0.60x0.60x0.60M3 = 400 Pits/Ha at 5 mtr Spacement For Model 3 - pit size 0.60x0.60x0.60M3 = 800 Pits/Ha at 3.5 mtr Spacement For Model 4 - pit size 0.60x0.60x0.60M3 = 100 Pits/Ha and - pit size 0.45x0.45x0.45M3 = 1500 Pits/Ha at 2.5 mtr Spacement For Model 5 - pit size 1.00x1.00x1.00M3 = 100 Pits/Ha at 10 mtr Spacement								
					SSR Rate	43.76 /cum		
Unit No	Range / Model	Name of the Village	Section	Quantity in Ha	Pits in Cu.m	Maximum Amount	EMD Amount	Remarks
6	Kollegal Range							
	Model 2	Uganiya	Sathegal Jageri	25	2,160.00	94,522.00		Works to be carried out as per the above Specification. The total amount payable shall be based on the actual work done as per the above specification and limited to the amount mentioned for each work.
					-	-		
	Model 3	Hosadoddi	P.G. Palya	10	1,728.00	75,617.00		
		Masibhovidoddi	P.G. Palya	10	1,728.00	75,617.00		
		Munigudidoddi	P.G. Palya	30	5,184.00	226,852.00		
		Utturu	P.G. Palya	30	5,184.00	226,852.00		
		Hosapalaiyam	P.G. Palya	10	1,728.00	75,617.00		
					-	-		
	Model 4	Masibhovidoddi	P.G. Palya	20	3,162.00	138,369.00		
		Uganiya	Sathegal Jageri	20	3,162.00	138,369.00		
		Munigudidoddi	P.G. Palya	20	3,162.00	138,369.00		
					-	-		
	Model 5	Masibhovidoddi	P.G. Palya	15	1,500.00	65,640.00		
		Uganiya	Sathegal Jageri	10	1,000.00	43,760.00		
		Hosapalaiyam	P.G. Palya	20	2,000.00	87,520.00		
				220		1,387,104	34,700	
9	Gundlupet Range							
	Model 2	Lokkere	Yelchetty	25	2,160.00	94,522.00		Works to be carried out as per the above Specification. The total amount payable shall be based on the actual work done as per the above specification and limited to the amount mentioned for each work.
					-	-		
	Model 3	Lokkere	Yelchetty	50	8,640.00	378,086.00		
					-	-		
	Model 4	Lokkere	Yelchetty	30	4,743.00	207,554.00		
					-	-		
	Model 5	Huliyammanagudi	Hangala	25	2,500.00	109,400.00		
		Lokkere	Yelchetty	10	1,000.00	43,760.00		
					-	-		
				140		833,322.00	20,800	
D) Tender for Pits as per the specification during the year 2006-07 under 12 Finance Commission								
Excavation of pits with vertically cut edges to make an uniform cube and heaping the excavated soil on the lower side of the pits (1/3 top soil on the upper side and lower side) in hard soil For Gap Planting - pit size 0.60x0.60x0.60M3 = 100 Pits/Ha at 10 mtr Spacement For Model EEA & CFA - pit size 0.60x0.60x0.60M3 = 100 Pits and - pit size 0.45x0.45x0.45M3 = 1500 Pits/Ha at 2.5 mtr Spacement								
					SSR Rate	43.76 /cum		
11	Gundlupet Range							
	EEA	Lokkere	Yelchetty	20	3,165.60	138,527.00		-Do-
	CFA	Suvarna Nagar	Yelchetty	20	3,165.60	138,527.00		
				40		277,054.00	6,900	
E) Tender for Soil and Moisture Conservation Works (Gully Checks) as per the specification during the year 2006-07 under KSFMB								
Providing and constructing rough stone revetment 55 cm. Thick as per design and drawing using stones not less than 30 cm. Thick with surface area of not less than 0.04 Sqmtr. with pin headers and wedged by spell as per specification over a layer of 15 cms. Thick granite/trap or basalt metal of 40mm and down size graded metal laid over 10 cms thick sand as per specification with an initial lead of 50m and lift of 1.5m etc., complete.								
					SSR Rate	170.00 /cum		
Unit No	Range / Model	Name of the Village	Section	Quantity in Ha	GC in Cu.m	Maximum Amount	EMD Amount	Remarks
14	Gundlupet Range							
	Model 3	Lokkere	Yelchetty	50	1,126.00	191,420.00		-Do-
	Model 4	Lokkere	Yelchetty	30	645.90	109,803.00		
				80	1,771.90	301,223.00	7,500	

F) Tender for Construction of Supporting Staff Twin Quarters as per the PWD SSR during the year 2006-07 under KSFMB								
					Unit COST 500,000.00 /No			
Unit No	Range / Model	Name of the Village	Section	Quantity in No		Maximum Amount	EMD Amount	Remarks
	Gundlupet Range							
15	Bachalli		Yelchetty	1		500,000.00	12,500	Plan of the building can be obtained from the office
G) Tender for Excavation of New EPT under Nature Conservation during the year 2006-07								
Excavation of elephant-proof trench of size top width 3.0 m bottom 1.0 m and vertical depth 2.0 M. with an initial lead up to 2 M. and depositing the excavated soil uniformly over the inner side of the elephant-proof trench and forming conical mound of height 1.5 m, including manually compacting the mound by deploying JCB / Hitachi excavators (3.00m+1.00m/2)*2.00m*1.00m @ Rs.36/Cmtr. as per SSR								
					SSR Rate 36.00 /cum			
Unit No	Range / Model	Name of the Village	Section	Quantity in Km.	EPT in Cu.m	Maximum Amount	EMD Amount	Remarks
19	Hanur Range							
				8	32,000	1,200,000.00		Remark as per unit no 9
				8	32,000	1,200,000.00	30,000	

Sd/-
Deputy Conservator of Forests
Kollegal Division, Kollegal.